

4 050108

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION,
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-22,286-00-00

NW NE NE, SEC. 28, T 14 S, R 16 ~~W~~ ^{XX}

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9394

Lease Name Furthmyer Well # 2

Operator: D-Oil, Inc.

County Ellis 110.24

Name & Address P.O. Box 278

Well Total Depth 3392 feet

Victoria, KS 67671

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 197

Abandoned Oil Well XXXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Co Tools License Number _____

Address _____

Company to plug at: Hour: 3:00PM Day: 31 Month: August Year: 19 90

Plugging proposal received from Alfred Dreiling

(company name) D-Oil Co. (phone) 913-735-9225

were: Order 400 sxs. 65/35 pos 8%gel and hulls.

Perf. Anhydrite and base of Dakota sand section.

8 5/8" at 197', 4 1/2" at 3392.

Perf at 400' and 990'

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXXXX Part _____ None _____

Operations Completed: Hour: 4:45PM Day: 31 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Ran tbg. to 2000' and pmp 55 sxs. 65/35pos 8%gel and 100# hulls. Pulled 1000' of tbg. and pump 80 sxs. 65/35pos 8%gel and 100# hulls until cement circ to surface. Pulled tbg. and tied onto surface pipe and pmp 50 sxs. of 65/35pos 8%gel and 50# hulls, Max Press 1000# SIP 600#. Tied onto annulus and pmp. 10 sxs. 65/35 pos 8% gel. Max 450#.

Remarks: B-J Hughes Cementing

INVOICED

If additional description is necessary, use BACK of form.

I (do ~~not~~) observe this plugging.

DATE: SEP 17 1990
CHK. NO. 29326

H.D.S.

Signed _____
(TECHNICIAN)

Herb Deines

SEP 10 1990
CONSERVATION DIVISION
WICHITA, KANSAS