

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23882-00-00  
Spot: S2SEW Sec/Twnshp/Rge: 25-14S-16W  
3070 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: BAUMRUCKER B Well Number: 1  
County: ELLIS Total Vertical Depth: 3380 feet

Operator License No.: 32875  
Op Name: CWB - CO  
Address: 1312 N. OAKMORE  
TULARE, CA 93274

Production Casing Size: 4.5 feet: 3379 125 SX CM 169.85  
Surface Casing Size: 8.625 feet: 221 135 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2003 2:30 PM  
Plug Co. License No.: 32875 Plug Co. Name: CWB - CO  
Proposal Rcvd. from: JAMES HERTEL Company: CWB - CO Phone: (785) 483-2627

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perfs 3335'-3338'; 3323'-3326'; 3311'-3313'.  
Dakota 53'-353'. Anydrite 914'-944'. Salt 1395'-1547'.  
07-31-84 - PF 926' cwc 300 sxs common.  
Tubing stuck in the hole at 1512'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/26/2003 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Big Creek Well Service RIH to 1470'.  
Allied tied onto tubing and pumped 80 sxs 60/40 pozmix neat to circulate cement into pit.  
Pulled tubing and tied onto casing and pumped 40 sxs 60/40 pozmix with 200# hulls.  
Max. P.S.I. 500#. S.I.P. 0#.  
Blew a hole in casing near surface.  
Tied onto backside - cement came out of hole near surface.  
Backside appeared to be full.

RECEIVED  
03-27-2003  
MAR 27 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #13273.

Plugged through: TBG

District: 04

Signed *Pat Staab*  
(TECHNICIAN)

INVOICED

Form CP-2/3

3-31-03

2003061355

MAR 27 2003

R. P. NIXON  
 207 W. 12TH ST.  
 HAYS, KS 67610  
 CONTR JAY-LAN CORP.  
 #1 11/8" BAUMRUCKER  
 25-14-16W  
 100' IN  
 C S/2 SE NW

GEOL DAN NIXON  
 FIELD BAUMRUCKER  
 CITY ELLIS  
 ELEV 1835 KB SPD 5/16/84  
 CARD 8/30/84  
 IP P 45 BO & 5 BWPD  
 (MARR/PLEAS) 3311-3313  
 NEW PAY

LOG	Tops	Depth/daum
ANH	914+	921
TOP	2800-	965
HEEB	3025-	1190
TOH	3044-	1209
LAN	3075-	1240
BKC	3295-	1460
PLEAS	3310-	1475
ARB	3322-	1487
PBTD	3318-	1483
RTD	3380-	1545

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

NOTE: CORRECTION 6/7/84 - ORIGINALLY FIRST REPORTED IN C  
 S/2 SE NW, #1 BAUMRUCKER

AP 1 15-051-23, 882  
 8 5/8 " 221/135SX, 4 1/2 " 3379/125SX  
 NO DSTS  
 MICT - CO, PF (ARB) 3335-38, AC 250G (15), SWB DWN, REC  
 1.25 BF (97% OIL) / 1ST HR, PF (ARB) 3323-26, AC 500G (15),  
 REG. 94 BF (17-20% OIL) / 1ST HR, NON-COMMERCIAL, SET BP  
 AT 3318', PF (PLEAS) 3311-13, AC 500G (15%), SWB DWN, REC  
 12 BF (20% OIL) / 1 HR, SQZ'D PES W/5 SX, CO GMIT, RE-PF  
 (PLEAS) 3311-13, AC 500G (15%), SWB DWN, REC 8 BF (100%  
 OIL) / 1ST HR, POP, P 45 BO & 5 BWPD, 5/21/84