

6 061840

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-24,001-00-00

SE, SEC. 25, T 14 S, R16 W/Ex

2310 feet from S section line

2160 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Baumracker Well # A-1

Operator: Oil Producers Inc of Ks.

County Ellis 109.04

Name & Address Box 8647

Well Total Depth 3355 feet

Wichita, Ks. 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 897

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc License Number 6050

Address Box 698 Great Bend, Ks. 67530

Company to plug at: Hour: 7:00 A.M. Day: 27 Month: April Year: 19 89

Plugging proposal received from

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: Order 200 sks 60/40 Poz 8% Gel 5 sks Hulls.

MAY 11 1989  
05-11-1989

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour 10:00 A.M. Day: 27 Month: April Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 897' w/450 sks. 4 1/2" set at 3354' w/110 sks.

Top perf at 3293'. Plugged bottom w/sand and 4 sks cement to 3250'. Shot pipe one time and recovered 2500'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 200 sks cement w/ 900 psi.

Remarks: By Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby acknowledge and agree to observe this plugging.

DATE 5-12-89

Signed [Signature] (TECHNICIAN) D

INV. NO. 26824

Gilbert G. Scheck