

6 21 201

API NUMBER 15-051-24005-00-00

SE, SEC. 19, T. 14 S, R. 16 W10

990 feet from N/S section line

1650 feet from W/E section line

Lease Name Kuhn Well # 1

County Ellis

Well Total Depth 3490 13.43 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 212

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9756

Operator: T.J.D. oil co.

Name & Address Box 127

Hays Ks.

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Dreiling oil co. License Number 5145

Address Victoria Ks.

Company to plug at: Hour: 11:AM Day: 3 Month: 9 Year: 19 84

Plugging proposal received from Bob Michaelson

(company name) Dreiling (phone) _____

were: order 180 sx. cement 50/50 portix 6% gel. 3% c.c.

1 sx. hulls 1. 8 5/8 plug 1. 5x Flow Seal

Heavy mud between all plugs

Pump cement down drill pipe

Elev. 1936 Anhydrite 1064-1108 Arbuckle 3466

Dakota 1775 Plugging Proposal Received by Paul F. Batthazor

161 = 460

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part (None)

Operations Completed: Hour: 4:PM Day: 3 Month: 9 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3480 for 30 min

25 sx. @ 3480

25 sx. @ 1080

100 sx @ 500 mixed with 15x. Flow Seal

10 sx @ 40

dumped 15x hulls pushed plug to 40'

Remarks: 10 sx in Rat hole. 10 sx in mouse hole - Allied

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

9-19-84
3765

SEP 20 1984
C9-104984

Signed Paul F. Batthazor (TECHNICIAN) SH
sep 7
28