

4-050168

TO: API number: 15-063-21,011-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202
E2 E2 NW /4 SEC. 34, 14 S, 27 W
3960 feet from S section line
2970 feet from E section line

Operator license# 5123 Lease Rohr well# B-4

Operator: Pickrell Drilling Co. Inc. County Gove

Address: 110 N. Market Suite 205 Well total depth 4298 feet ^{139.68}
Wichita, Kansas 67202 Conductor Pipe: _____ inch @ _____ feet
(316)262-8427 Surface Pipe: 8 5/8 inch @ 290 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: _____

Company to plug at: Hour: AM Day: 11 Month: August Year: 1993

Plugging proposal received from: Jack Gurley

Company: Pickrell Drilling Co. Inc. phone: _____

Were: 8 5/8 surface casing set @ 290 with 180 sks. cement
4 1/2 production casing set @ 4288 with 150 sks. cement
Open hole 4288-98
Elevation 2458 PBD 4298 TD 4298 Anhydrite 1885

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00, Day: 11, Month: August, Year: 1993

Actual plugging report: Tied onto backside pumped 0 sks. 60/40 poz 10% gel 500 max. psi and 500 shut in psi. Tied onto 4 1/2" csg. pumped 220 sks. 60/40 poz 10% gel 500 lbs. hulls at 1500 max psi & 1500 shut in psi.

Remarks: _____

I did [xx] did not [] observe the plugging. Marvin Miller

DATE SEP 01 1993 HO 385 36
Form CP-2/3

STATE CORPORATION COMMISSION
RECEIVED
AUG 30 1993
CONSERVATION DIVISION
WICHITA, KANSAS
08-30-93