

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-063-20709-00-00
NW, Sec. 33, T 14 S, R 27 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692

Lease Name Coberly Well # 1

Operator: Am Petrofina of Texas
Name & Address 4613 Jacksboro Hwy.
Wichita Falls, Tx.

County Gove

Well Total Depth 4350 feet 141.77

Conductor Pipe: Size _____ feet

Surface Casing: Size 8⁵/₈ feet 961

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Company License Number 5657

Address Wichita, Ks.

Company to plug at: Hour: 11:00 AM Day: 16 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Dave Roddy

(company name) Am. Petrofina (phone) _____

were: Order 195 sks cement 50/50 pozmix 6% Gel 3% cal.cl

1 sk hull 1-8⁵/₈ plug

Heavy mud between all plugs

Pump cement down drill pipe

Elevation 2465 Anhydrite 1900-40 Arbuckle No Dakota 1850

Signed Dale F. Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:30 PM Day: 16 Month: February Year: 19 84

ACTUAL PLUGGING REPORT Circulate @ 1930 for 30 minutes

1st plug 25 sks @ 1930

2nd plug 140 sks @ 1000 - 1 sk hulls push plug to 40'

3rd plug 15 sks @ 40

15 sks in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION

Remarks: I did check this plug.

Cementing Co. - Allied

FEB 27 1984
02-27-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~do not~~) observe this plugging.

Signed Dale F. Balthazor
(TECHNICIAN)

3-2-84
0490
2.15