

To: 6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-20,685-00-00
SE SE SE SEC. 31, T 14 S, R 27 W/E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: Donald C. Slawson
Name & Address Douglas Bldg.
104 S. Broadway
Wichita, Ks. 67202

Lease Name Coberly Well # BD 1
County Gove 143.16
Well Total Depth 4405 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 22 Month: Dec Year: 19 87

Plugging proposal received from Ronnie
(company name) Kelso (phone) _____

were: 8 5/8" at 300' w/250 sks cwc. 4 1/2" at 4404' w/125sks. PBTD 4354'. Perf 4208' -
11'. Order sand and Common Cement. Pull pipe. Order 150 sks ATL 65/35 Poz 10%
Gel 2% Dical Cement Blend. Allied Cement Co, Walker Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00AM Day: 22 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4155' w/4 sks Common Cement on sand w/bailer.
2 shots at 3000' and 2710'. Recovered 2710' of 4 1/2" casing. Squeeze 8 5/8" casing
w/150 sks Cement Blend w/5 sks Hulls mixed in. Max Psi 500#. Close in Psi 500#.
Plug complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOLVED
I hereby agree to preserve this plugging.

DATE 1-20-88

FILE NO. 19616

Signed Carl Goodrow
(TECHNICIAN)