

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-063-20, 625-00-00

NE, Sec. 30, T14 S, R27 A1E

1640 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6777

Lease Name Slater Well # 1

Operator: Childs Oil & Exploration  
Name & Address Rt. 2, Box 214, Rogersville, Mo.  
65742

County Gove

Well Total Depth 4314 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 165'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murphy Drilling Co. License Number 602

Address 617 Union Center, Wichita, Ks 67202

Company to plug at: Hour: 1:00 PM Day: 14 Month: 11 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Keith Hampelt

(company name) Murphy Drilling Co. (phone) 316-267-3241

were: Order 180 sacks 50 permix - 6% cel. - 3% lab. ll. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug @ 1900' w/ 20 sacks  
2nd plug @ 950' w/ 100 sacks.  
3rd plug @ 200' w/ 40 sacks.  
4th plug - solid bridge of hulls + plug @ 45' w/ 10 sacks.

Circulated 10 sacks in rat hole.

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00 PM Day: 14 Month: 11 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 165' cas. w/ 125 sacks Common - 2% cel. - 3% lab. ll.

Ordered 180 sacks 50 permix - 6% cel. - 3% lab. ll. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug @ 1900' w/ 20 sacks  
2nd plug @ 950' w/ 100 sacks,  
3rd plug @ 200' w/ 40 sacks, 4th plug - solid bridge of hulls + plug @ 40' w/ 10 sacks

Circulated 10 sacks in rat hole

Remarks: No. Arbuckle

RECEIVED STATE CORPORATION COMMISSION NOV 22 1982 CONSERVATION DIVISION Wichita Kansas 11-22-82

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

12-20-82 1864-W Signed [Signature] (TECHNICIAN)