

6010155

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-167-22405-00-00

NW, SEC. 8, T. 14 S., R. 12 W/E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6212

Lease Name Mahoney Well # 1

Operator: Ivan Holt

County Russell

Name & Address West Hwy 40

Well Total Depth 3300 10% 35' feet

Russell

Conductor Pipe: Size \_\_\_\_\_ feet

Kansas

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil opp. License Number 824-1

Address Box 506 Russell Ks.

Company to plug at: Hour: PM Day: 30 Month: 6 Year: 19 84

Plugging proposal received from Greg Flax

(company name) Emphasis oil opp. (phone) \_\_\_\_\_

work: order 170 sx. cement 50/50 pozmix 6% gel, 3% cal. cl.

1-sx. hulls 1-8 5/8 plug 1-SX Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 1797 Anhydrite 726-58 Arbuckle - no.

Dakota 1650 Plugging Proposal Received by Dale F. Balthazor

147 = 450

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part (None)

Operations Completed: Hour: 2:30 AM Day: 1 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 740 for 10 mi.

50 sx @ 740

100 sx @ 450 mixed with 1-sx. Flow Seal

Dumped 15x hulls, pushed plug to 40'

10 sx @ 40

10 sx in Rat Hole

Remarks: cementing to sun

(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
07-09-1984  
JUL 09 1984

CONSERVATION DIVISION  
Wichita, Kansas

Signed Dale F. Balthazor  
(TECHNICIAN)

July 6 1984  
18