

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

CP-4
Form CP-4
March 2000

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5447
Name: Oxy USA, Inc.
Address 1: PO Box 2528
Address 2: _____
City: Liberal State: Ks Zip: 67905
Contact Person: Kenny Andrews
Phone: (620) 629 4232
Type of Well: (Check one) Oil Well Gas Well OG D&A Cethode
 Water Supply Well Other: _____ SWD Permit #: _____
 ENM Permit #: _____ Gas Storage Permit #: _____
Is ACC-1 Riled? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Morrow Depth to Top: 2572 Bottom: 2576 T.D. 6000

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15- 129-21074 00 00
Spot Description: SE SW
SW NE SE SW Sec. 31 Twp. 31 S. R. 39 East West
696 Feet from North / South Line of Section
3169 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW BE SW
County: Morton
Lease Name: Milburn A Well #: 2
Date Well Completed: 4-29-91 spud
The plugging proposal was approved on: 10-2-09 (Date)
by: Ken Jahlik (KCC District Agent's Name)
Plugging Commenced: 11-3-09
Plugging Completed: 11-4-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Plugged Out
			20	45	—
			8 5/8	1721	—
			5 1/2	6001	—

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb. hulls + 25 sx cmt. to plug perfs from 4572 to 4372. Measured stretch - stuck @ 100. Records showed cmt circ. to surface from DV @ 3100. Ran 2 3/8 to 1750. Mixed 25 sx 1750 to 1550. Mixed 67 sx 600 to 0. Mixed 18 sx down annulus from 108 to 0. Cut 8 5/8 + 5 1/2 + capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515
Name of Party Responsible for Plugging Fees: Oxy USA Inc. PO Box 2528 Liberal, KS 67905
State of Kansas County: Seward, ss.
Kenny Andrews Employee of Operator or Operator on above-described well
(Print Name)

being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Kenny Andrews

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 17 2010
3-17-10
CONSERVATION DIVISION
WICHITA, KS