

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34318 Name: Berexco LLC Address 1: PO Box 20380 Address 2: City: Wichita State: KS Zip: 67208 + 1380 Contact Person: Evan Mayhew Phone: (316) 265-3311

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 025-21490-00-00 Spot Description: SW SE NE SE Sec. 4 Twp. 30 S. R. 22 East West 1,450 Feet from North South Line of Section 429 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Clark Lease Name: Charlotte Well #: 1-4 Date Well Completed: 08 December, 2009 The plugging proposal was approved on: 07 December, 2009 (Date) by: Jerry Stapleton (KCC District Agent's Name) Plugging Commenced: 08 December, 2009 Plugging Completed: 08 December, 2009

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8-5/8", 611', none.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 60/40 POZ, 4% gel through open - ended drill pipe as follows: 50 sacks at 1350 ft, 75 sacks at 600 ft, 50 sacks at 300 ft, 20 sacks at 60 ft (to surface) 30 sacks in rathole, 20 sacks in mousehole. All cement from Allied Cementing Co., LLC. Plugging completed at 12:10 PM.

Note that Induction Log indicated bottom joint of surface casing was knocked off and fell down hole. Top of joint is at 1360'.

RECEIVED

FEB 23 2010 2-23-10 KCC WICHITA

Plugging Contractor License #: 34317 Name: Beredco LLC Address 1: PO Box 20080 Address 2: City: Wichita State: KS Zip: 67208 + Phone: (316) 265-2856

Name of Party Responsible for Plugging Fees: Berexco LLC State of KS County, Sedgwick, ss. Richard R. Smith (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Richard R. Smith