

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 7383  
Name: Grady Bolding Corporation  
Address 1: P.O. Box 486  
Address 2: 114 N Main  
City: Ellinwood State: KS Zip: 67526 +  
Contact Person: Grady Bolding  
Phone: (620) 564-2240 or 620-797-0115 (cell)  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3691 Bottom: 3696 T.D. 3698 1/2  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 051-20532 00-00  
Spot Description: \_\_\_\_\_  
NE SE NW Sec. 17 Twp. 12 S. R. 17  East  West  
680 3598 Feet from  North  South Line of Section  
2310 3012 Feet from  East  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: Schmeidler A Well #: 6  
Date Well Completed: 12/18/1969  
The plugging proposal was approved on: 02/04/2010 (Date)  
by: Pat Staab (KCC District Agent's Name)  
Plugging Commenced: 02/08/2010  
Plugging Completed: 02/08/2010 2:45 p.m.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle	oil	Production	5 1/2"	3693'	none
		Surface	8 5/8"	210'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Professional Pulling Services RIH with tubing to 3400'  
Quality Cementing rigged to tubing - mixed and pumped 13 sxs gel - followed with 50 sxs 60/40 pozmix with 250# hulls mixed in.  
Pulled tubing to 1850". Quality rigged to tubing and pumped 170 sxs cement with 250# hulls mixed in to circulate cement area.  
Pulled tubing - rigged to 8 5/8" casing with swedge - pumped 5 sxs cement. Max PSI 500#. SIP 500#.  
Topped off 5 1/2" casing with 20 sxs cement. Hole standing full.

RECEIVED  
FEB 23 2010

KCC WICHITA

Plugging Contractor License #: 32810 Name: Professional Pulling Service LLC  
Address 1: P.O. Box 486 Address 2: \_\_\_\_\_  
City: Hays State: KS Zip: 67601 +  
Phone: (785) 628-7443  
Name of Party Responsible for Plugging Fees: Grady Bolding Corporation  
State of Kansas County, Ellis, ss.  
Grady Bolding  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Grady Bolding