

4-110083

15-051-19004-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 7-19-1957

NE SE NE /4 SEC. 36 , 13 S, 20 W
3630 feet from S section line
330 feet from E section line

Operator license# 100
Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #200024-007

Lease: M.R. Engel Well # 7
County: Ellis
Well total depth 3868 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 317 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 2:30 P.M. Day: 18 Month: January Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.
Ordered 400 sxs cement and 20 sxs gel with 800# hulls.
Plug through casing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:00 P.M., Day: 18, Month: January, Year: 2000

Actual plugging report: 10 3/4" S.P. set at 217' w/N/A sxs cement. 7" casing at 3862' w/N/A sxs cement. Perforated at 750' - 1550' - 2175'. Tied to 7" casing and pumped 50 sxs cement with 300# hulls. Pumped 20 sxs gel with 200# hulls. Pumped 220 sxs cementw/200# hulls to Max. P.S.I. 500#. S.I.P. 200#. Tied to 10 3/4" x 7" annulus and pumped 50 sxs cement with 100# hulls to Max. P.S.I. 400#. S.I.P. 100#. Total 320 sxs 60/40 pozmix with 10% gel - 20 sxs gel and 800# hulls.

Dakota at 462' - 748'. Cedar Hills at 983' - 1218'. Anhy at 1523' - 1566'.
Salt Section at 1873' - 2148'.

Tapped well off w/95 sxs 1-19-00 P.M.

Remarks: Allied Cementing. Cheyenne Oil Service - water.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES , NO
Plugged through TUBING , CASING X. Elevation: 2227 GL

I did[X] / did not[] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
(agent)
JAN 31 2000
1-31-00
Form CP-2/3
Wichita, Kansas
NO.
R

TEXAS COMPANY

#7 M R ENGEL

36-13-20W
NE SE-NE

Contr STICKLE DRLG

ELLIS County

E 2232^{RB} Comm. Comp. 7-19-57 IP 120 BOPD

Tops	Depth	Datum
TOP	3217	-985
HEEB	3476	-1244
TOR	3496	-1264
LANS	3516	-1284
B/KC	3764	-1532
ARB	3860	-1628
TD	3868	-1636

Casing
 10" 317
 7" 3862
 CO 3868

IRVIN POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS