

4-110082

15-051-02916-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 5-11-1957

NW NW NE /4 SEC. 36 , 13 S, 20 W  
4950 feet from S section line  
2310 feet from E section line

Operator license# 100

Lease: M.R. Engel Well # 6

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #200024-006

County: Ellis  
Well total depth 3841 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 1240 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 1:00 P.M. Day: 18 Month: January Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.  
Ordered 400 sxs cement and 20 sxs gel with 800# hulls.  
Plug through casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:30 P.M., Day: 18, Month: January, Year: 2000

Actual plugging report: 10 3/4" S.P. set at 1240' w/N/A sxs cement. 7" casing at 3837' w/N/A sxs cement. Perforated at 750' - 1550' - 2175'. Tied to 7" casing and pumped 50 sxs cement with 300# hulls. Pumped 20 sxs gel with 200# hulls. Pumped 100 sxs cement to Max. P.S.I. 800#. S.I.P. 500#. Tied to 10 3/4" x 7" annulus and pumped 50 sxs cement with 200# hulls to Max. P.S.I. 400#. S.I.P. 400#. Total 200 sxs 60/40 pozmix with 10% gel - 20 sxs gel and 700# hulls.

Remarks: Allied Cementing. Cheyenne Oil Service - water.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING X. Elevation: 2200 GL

I did [ X ] / did not [ ] observe the plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
(agent)

IAN 31 2000  
1-31-00

Form CP-2/3

(Handwritten initials)

TEXAS COMPANY

#6

M R ENGEL

36-13-20W  
NW NW NE

Contr. STICKLE DRLG

ELLIS

County

E 2200

Comm

5-11-57

Comp

6-14-57

IP

269 BOPD/ARB  
PERM PMP

Tops	Depth	Datum
TOP	3191	-991
HEEB	3114	-1214
LANS	3186	-1286
B/KC	3736	-1536
ARB	3836	-1636
TD	3811	-1611


Casing

10" 1240

7" 3837

CO 3814: SWB 7 1/2 BO, TR WTR/6  
HRS, 40' OB: PMP 73 BO, TR WTR/  
8 HRS

PLEASANT NORTH POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS