

4-110079

15-051-19002-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 10-28-1956

SW SE NE /4 SEC. 36 , 13 S, 20 W
2970 feet from S section line
990 feet from E section line

Operator license# 100

Lease: M.R. Engel Well # 1

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #200024-001

County: Ellis

Well total depth 3851 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 318 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 1:00 P.M. Day: 20 Month: January Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.
Ordered 400 sxs cement and 20 sxs gel with 800# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:00 P.M., Day: 20, Month: January, Year: 2000

Actual plugging report: 10 3/4" S.P. set at 318'. 7" casing at 3841'. Perforated at 750' - 1550' and 2175'. Ran tubing to 3800' - pumped 12 sxs gel with 100# hulls - pumped 50 sxs cement with 100# hulls. Pulled to 2200' and pumped 120 sxs cement with 400# hulls. Pulled tubing to 1000' and circulated with 65 sxs cement and 150# hulls. Tied to 5 1/2" liner and topped off with 10 sxs cement - pressured to Max. P.S.I. 700#. S.I.P. 500#. Tied to 11 3/4" x 7" annulus - pumped 50 sxs cement with 50# hulls to Max. P.S.I. 200#. S.I.P. 100#. Total 295 sxs 60/40 pozmix - 10% gel - 12 sxs gel - 800# hulls.

Remarks: Allied Cementing. Cheyenne Oil Service - water.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING X, CASING . Elevation: 2209 GL

I did[X] / did not[] observe the plugging.

Reggie L. Moses
STATE CORPORATION COMMISSION (agent)

Form CP-2/3

JAN 31 2000
1-31-00
CONSERVATION DIVISION
Wichita, Kansas

(R)

TEXAS COMPANY

#1 M R ENGEL

20-12-20W
SW SE NE

Contr. STICKLE DRLG

ELLIS

County

E. 2211 Comm. 10-28-56 Comp. 12-7-56 IP 140 BOPD/ARB

Tops	Depth	Datum
HEEB	3462	-1251
LANS	3504	-1293
B/KC	3748	-1537
CONG	3804	-1593
ARB	3847	-1636
TD	3851	-1640

Casing

10" 318

7" 3841

CO TD: SWB 25 BO, NW/7 HRS

DD 3851: SWB 60 BO, NW/15

HRS: TST: DD 3851

PLEASANT POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

10-18-56