

4-110085

15-051-02912-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 12-2-1956

NE SW NE /4 SEC. 36, 13 S, 20 W  
3630 feet from S section line  
1650 feet from E section line

Operator license# 100

Lease: M.R. Engel Well # 2

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13th Street  
Hays, Kansas 67601  
Control #200024-002

County: Ellis  
Well total depth 3844 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 318 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 8:30 A.M. Day: 20 Month: January Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.  
Ordered 400 sxs cement and 20 sxs gel with 800# hulls.  
Plug through tubing.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:30 A.M., Day: 20, Month: January, Year: 2000

Actual plugging report: 10 3/4" S.P. set at 318'. 7" casing at 3841'.  
Perforated at 750' - 1525' (Hit bridge). Tied to tubing and pumped 80 sxs cement with 400# hulls. Pulled tubing to 700' and circulated with 130 sxs cement and 350# hulls. Pulled all tubing and tied to 10 3/4" x 7" annulus - pumped 50 sxs cement with 50# hulls to Max. P.S.I. 200#. S.I.P. 100#. Tied to 7" casing and pumped 50 sxs cement to Max. P.S.I. 400#. S.I.P. 200#. Total of 310 sxs 60/40 pozmix with 10% gel and 800# hulls.  
Dakota at 429' - 715'. Cedar Hills at 950' - 1185'. Anhy at 1492' - 1535'.  
Salt Section at 1840' - 2115'.

Remarks: Allied Cementing. Cheyenne Oil Service - water.  
Condition of casing (in hole): GOOD BAD X Any plug: YES X NO  
Bottom plug (in place): YES, CALC X, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING Elevation: 2192 GL

I did [ X ] / did not [ ] observe the plugging.

STATE CORPORATION COMMISSION (agent)  
Form CP-2/3

JAN 31 2000  
1-31-00  
CONSERVATION DIVISION  
Wichita, Kansas

(R)

TEXAS COMPANY

#2 ENGEL

36-13-20W  
NE SW NE

Contr. STICKLE DRLG

ELLIS

County

E. 2197 Comm. 12-2-56 Comp. 1-4-57 IP 237 BOPD

Tops	Depth	Datum	Casing
HEEB	3451	-1254	10" 318
LANS	3492	-1295	7" 3841
B/KC	3740	-1513	CO TD: SWB 32' 80, 2 BW: ACID
CONG	3809	-1612	250: SWB 180' 80, NW/10 HRS
ARB	3840	-1613	PMP 180 BOPD, NW
TD	3844	-1647	

PLEASANT N

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS