

4-110081

15-051-02915-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 3-3-1957

NE NW NE /4 SEC. 36 , 13 S, 20 W  
4950 feet from S section line  
1650 feet from E section line

Operator license# 100 101

Lease: M.R. Engel Well # 5

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #200024-005

County: Ellis  
Well total depth 3812 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 318 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 8:30 A.M. Day: 21 Month: January Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.  
Ordered 400 sxs cement and 20 sxs gel with 800# hulls.  
Plug through tubing.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All  , Part  , None

Completed: Hour: 2:00 P.M. , Day: 21 , Month: January , Year: 2000

Actual plugging report: 10 3/4" S.P. set at 318'. 7" casing at 3808'.  
Perforated at 750' - 1550' - 2175'. Ran tubing to 3627' and pumped 15 sxs gel and 50 sxs  
cement with 200# hulls. Pulled tubing to 2200' and pumped 120 sxs cement with 250# hulls.  
Pulled tubing to 1000' and circulated with 120 sxs cement and 100# hulls. Tied to 7" casing  
and squeezed 55 sxs cement to Max. P.S.I. 500#. S.I.P. 300#. Tied to 7" x 10 3/4" annulus  
with 50 sxs cement with 50# hulls. Total 395 sxs 60/40 pozmix - 15 sxs gel and 600# hulls.

Remarks: Allied Cementing. Cheyenne Oil Service - water.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING  , CASING  . Elevation: 2165 GL

I did  / did not  observe the plugging.

Raymond Moses  
RECEIVED (agent)  
STATE CORPORATION COMMISSION Form CP-2/3

JAN 31 2000  
1-31-00  
CONSERVATION DIVISION  
Wichita, Kansas

(R)

TEXAS COMPANY

#5 ENGEL

36-13-20W  
NE NW NE

Contr. STICKLE DRLG

ELLIS County

E 21 70 Comm. 3-3-57 Comp. 5-3-57 IP 240 BOPD/ARB  
PHY POT

Tops	Depth	Datum
ANH	1464	706
TOP	3162	-992
HEEB	3415	-1245
TOR	3435	-1265
LANS	3457	-1287
B/KC	3708	-1538
MARM	3744	-1574
CONG	3787	-1617
ARB	3807	-1637
ID	3812	-1642

Casing  
10" 318  
7" 3808

CO 3812: FU 1200' 0/4 HRS  
87 BO, NW/8 HRS

PLEASANT NORTH POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

290  
33  
375