

4-110084

15-051-02918-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 9-1-1957

NE NE NE /4 SEC. 36, 13 S, 20 W
4950 feet from S section line
330 feet from E section line

Operator license# 100

Lease: M.R. Engel Well # 8

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #200024-008

County: Ellis
Well total depth 3856 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 9 Inch @ 457 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 8:30 A.M. Day: 19 Month: January Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.
Ordered 400 sxs cement and 20 sxs gel with 800# hulls.
Plug through tubing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:00 A.M., Day: 19, Month: January, Year: 2000

Actual plugging report: 10 3/4" S.P. set at 457' w/N/A sxs cement. 7" casing at 3815' w/N/A sxs cement. Perforated at 750' - 1400' (Hit bridge). Ran tubing to 1400' and pumped 80 sxs cement with 300# hulls. Pulled tubing to 700' and circulated with 100 sxs cement and 200# hulls. Pulled all tubing and tied to 7" and squeezed 25 sxs cement with 50# hulls to Max. P.S.I. 550#. S.I.P. 550#. Tied to 10 3/4" x 7" annulus and squeezed 30 sxs cement with 50# hulls to Max. P.S.I. 500#. S.I.P. 200#. Total of 235 sxs 60/40 pozmix with 10% gel and 600# hulls.

Dakota at 442' - 728'. Cedar Hills at 963' - 1198'. Anhy at 1503' - 1546'.
Sal Section at 1853' - 2128'. RECEIVED STATE CORPORATION COMMISSION

Remarks: Allied Cementing. Cheyenne Oil Service - water.
Condition of casing(in hole): GOOD BAD X Anhy plug: YES X
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: 2207 GL

I did [X] / did not [] observe the plugging.

Regan L. Moses (agent)

Form CP-2/3



THE TEXAS COMPANY

#8 ENGEL

36-13-20W
NE NE NE

Contr. STICKLE DRILG CO

ELLIS County

E. 22 1/2 RB Comm 9-1-57

Comp. 10-18-57 IP

25 BOPD

Tops	Depth	Datum
TOP	3201	-989
HEEB	3155	-1213
TOR	3170	-1258
LANS	3198	-1286
R/KC	3712	-1530
ARB	3813	-1601
TD	3856	-1644

Casing

9" 457

5" 3815

DP: CO TD: 2400' FIH: SWB

163 BO, NW/8 HRS: 25 BO/24 HR

IRVIN POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS