

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02910-00-00  
Spot: CS2NENW Sec/Twnshp/Rge: 36-13S-20W  
4290 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: ENGEL A Well Number: 2  
County: ELLIS Total Vertical Depth: 3868 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 216  
Production: Size 5.5 feet: 3864  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/03/2001 9:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC.  
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 726-3411

Proposed Plugging Method: According to KCC Rules & Regulations.  
Perforate at 825' - 1550' - 2100'.  
Plug thru tubing.  
Ordered 350 sxs cement and 800# hulls.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/03/2001 11:45 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 216'. 5 1/2" casing at 3864'.  
2 1/2" tubing cemented in casing.  
Perforated at 825' - 1550' - 2100'.  
Tied to 2 1/2" tubing and squeezed 15 sxs cement to 1000# - locked up immediately.  
Tied to 2 1/2" x 5 1/2" and squeezed 5 sxs cement to 500#.  
Tied to 8 5/8" x 5 1/2" annulus - squeezed 10 sxs cement to 300#.  
Total of 30 sxs 60/40 pozmix - no hulls.

RECEIVED  
STATE CORPORATION COMMISSION

APR 17 2001  
4-17-01

Remarks: ALLIED CEMENTING COMPAN. STEWART TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

APR 16 2001

W. J. COPPINGER

#2 ENGEL 'A'

S2 NE NW

Contr. COPPINGER DRLG

ELLIS County

E 222 $\frac{1}{2}$  RB Comm. 1-7-57

Comp.

3-29-57 IP

119 BOPD/ARB

PHY POT

Tops	Depth	Datum
ANH	1520	704
HEEB	3174	-1250
TOR	3197	-1273
LANS	3517	-1293
B/KC	3780	-1556
ARB	3864	-1640
TD	3868	-1644

Casing

8" 216


5" 3864

DST 3860-66/1 $\frac{1}{2}$  HR, 40' FR 0

60' MDY 0, BHP 1110#

SWB 4 BOPH/8 HRS

PLEASANT POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS