

4-110086

15-051-19003-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- 3-8-1957

SW NE NE /4 SEC. 36, 13 S, 20 W  
4290 feet from S section line  
990 feet from E section line

Operator license# 100  
Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #200024-003

Lease: M.R. Engel Well # 3  
County: Ellis  
Well total depth 3827 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 318 feet

Aband. oil well X, Gas well       , Input well       , SWD       , D & A       

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 3:00 P.M. Day: 19 Month: January Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.  
Ordered 400 sxs cement and 20 sxs gel with 800# hulls.  
Plug through tubing.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All  ], Part [    ], None [    ]

Completed: Hour: 6:00 P.M., Day: 19, Month: January, Year: 2000

Actual plugging report: 10 3/4" S.P. set at 318'. 7" casing at 3823'.  
Perforated at 750' - 1550' - 2175'. Ran tubing to 3450' - pumped 15 sxs gel and 50 sxs  
cement with 200# hulls. Pulled tubing to 2430' - pumped 120 sxs cement with 150# hulls.  
Pulled tubing to 1000' and circulated with 180 sxs cement and 200# hulls. Tied to 10 3/4" x  
7" annulus and squeezed 50 sxs cement with 50# hulls to Max. P.S.I. 400#. S.I.P. 100#. Tied  
onto 7" casing and topped off with 40 sxs cement. Total of 440 sxs 60/40 pozmix with 10% gel  
and 15 sxs gel with 600# hulls.

Remarks: Allied Cementing. Cheyenne Oil Service - water.  
Condition of casing (in hole): GOOD        BAD  Anhy. plug: YES  NO         
Bottom plug (in place): YES       , CALC , NO        Dakota plug: YES , NO         
Plugged through TUBING , CASING       . Elevation: 2194 GL

I did  / did not  observe the plugging.

Robert L. Moses  
STATE CORPORATION COMMISSION (agent)

Form CP-2/3

JAN 31 2000  
1-31-00  
CONSERVATION DIVISION  
Wichita, Kansas

(R)

TEXAS COMPANY

#3 M R ENGEL

36-13-20W  
SW NE NE

Contr. STICKLE DRLG

ELLIS County

E 2199 Comm.

Comp. 3-8-57

IP 249 BOPD/ARB  
PHY POT

Tops	Depth	Datum
ANH	1492	707
TOP	3198	-999
HEEB	3447	-1248
TOR	3468	-1269
LANS	3488	-1289
B/KC	3747	-1548
CONG	3807	-1608
ARB	3826	-1627
TD	3827	-1628

Casing  
10" 318  
7" 3823

DST 3670-80/1 HR, 27' DRLG  
MUD, BHP 720#  
CO: DD 3827: FU 1200' 0/3  
HRS: SWB 147 BO, NW/9 HRS  
PMP 231 BO, NW/24 HRS

PLEASANT NW. POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS