

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-02911-00-00

NE-NE-NW Sec. 36, T 13 S, R 200 1/2

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name ENGLE Well # A" 3

Operator: LADD PETROLEUM CORP.
Name & Address 830 DENVER CLUB BLDG.
DENVER, COLORADO,
80202

County ELLIS

Well Total Depth 3853 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 210

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON CEMENTING License Number _____

Address 1100 EAST 8th ST. HAYS KANS. 67601

Company to plug at: Hour: 2:00 PM Day: 7th Month: MARCH Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO WARREN IRVIN

(company name) LADD PETROLEUM (phone) 316-792-3591

were: 8 5/8" 210^{ft} SR. CUL #125st, 5 1/2" SET @ 3843^{ft} #100st CMT.

NO PUG BACK - OPEN HOLE 10^{ft} - NO PIPE RECOVERY - TEMP. SERV.

CMT. 485^{ft} FROM TOP. ORDER 275st 50st FORMIX 4% CCL-3% CACL.

4st HULLS AND 5 1/2" PUG. PUMP IN WITH PUMP TRUCK.

PRESSURE ANNULUS BETWEEN 5 1/2" AND 8 5/8" CSG. WITH CMT. AND

LOAD 5 1/2" CSG. WITH CMT.

Signed Warren Irvin
(TECHNICIAN) 0012

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:20 PM Day: 7th Month: MARCH Year: 1983

ACTUAL PLUGGING REPORT ORDERED 275st 50st FORMIX 4% CCL-3% CACL. & 4st HULLS.

PUMPED 85st CMT. AND 2st HULLS IN ANNULUS. MAX. PRESSURE 500^{PSI}

PUMPED 190st CMT. AND 2st HULLS IN 5 1/2" CSG.

MAX. PRESSURE 1500^{PSI} (CEMENTED BY HALLIBURTON)

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

3-21-83
MAR 21 1983

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did) / ~~did not~~ observe this plugging.

Signed Warren Irvin
(TECHNICIAN) 0012

FORM CP-2/3
Rev. 9-82

DATE 3-30-83

WELL NO. 3858-W