

To: **6 002183**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-05256-0000  
SE, SEC. 15, T. 11 S, R. 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

330 feet from S section line

2310 feet from E section line

Operator: Oil Producers Inc.

Lease Name Peavey Well # 2

Name & Address Box 8647

County Ellis 113.56

Wichita, Kansas 67208

Well Total Depth 3494 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8" feet 134

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services Inc. License Number \_\_\_\_\_

Address Box 428 Hays, Ks. 67124

Company to plug at: Hour: 1:00 PM Day: 14 Month: Feb Year: 19 90

Plugging proposal received from Brad Siroky

(company name) Oil Producers Inc. (phone) 316-681-0231

were: Order 350 sks 65 /35 poz 8% gel 5 sks hulls.

D. V. from 1100' to surface.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30PM Day: 14 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT 8" set at 134' w/75 sks. 5" set at 3495' w/150 sks.

Top perf at 3202'. 2" run tubing to 3000' and spotted cement w/165 sks. Pulled tubing to 1233' and circulated cement to surface w/90 sks. Pulled all tubing.

Hooked onto 5 1/2" and pumped 28 sks cement w/400 psi. 8" - 9 sks cement w/200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: FFB 23 1990  
By Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICE

(did/did not observe this plugging.)

2-26-90

Signed Gilbert G. Scheck  
TECHNICIAN  
Gilbert G. Scheck

27569

APR 17 1990

75-051-05256-000

15-11-18W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg. Wichita, Kansas

Company. H. H. BLAIR, ET AL  
Farm. Opdyke "A" No. 2

SEC. 15 T. 11 R. 187  
S. 32

Total Depth. 3496'  
Comm. 10-4-47 Comp. 10-19-47  
Shot or Treated.  
Contractor. H. H. Blair  
Issued. 12-27-47

County. Ellis  
KANSAS



Elevation. 1947 feet

Production. Pot. 3000 bbls.

Figures indicate bottom of formations.

clay	184
shale & shells	470
shale	500
sand	635
iron & sand	651
sandy shale	740
sand	1065
sand red rock	1155
sand & shale	1224
anhydrite	1265
shale & lime shells	1375
shale & sand	1575
salt & shale	1820
shale	1888
shale & lime shells	1965
shale	2190
lime & shale	2570
sand	2585
shale & lime	2470
shale	2760
shale	2035
shale & lime	3010
lime	3465
shale	3493
lime	3496

Total Depth

T.D.S.