

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW SW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-20,727-00-00
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430
Operator: Energy Three Inc.
Name & Address: Box 1505
Great Bend, Ks, 67530

Lease Name Mendenhall Well # B-1
County Gove 141.38
Well Total Depth 4350 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 27 Month: July Year: 19 88

Plugging proposal received from Dallas

(company name) Kelso (phone) _____

were: 8 5/8" set at 261' w/165 sks cwc. 4 1/2" set at 4349' w/225 sks.

PRTD 4333' Perf 4142' - 46'. Order sand and Common Cement.

Pull pipe. Order 200 sks Cement Blend w/6 sks Hulls. Allied Cement Co.
Wellbrock Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 PM Day: 27 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Sand back to 4100' w/4 sks Common Cement on sand w/bailer.

One shot recovered 2800' of 4 1/2" casing.

Squeezed 8 5/8" w/200 sks Cement Blend w/600# Hulls mixed in w/1 sk C.C.

Added to Blend. To max Psi 400#. Close in Psi 400#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1988

Remarks: 2490 GL
(If additional description is necessary, use BACK of this form.)

INVOLVED
Observe this plugging.

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)

DATE 7-27
REV. NO. 1988