

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20487-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 30-18S-34W
1184 feet from S Section Line, 4916 feet from E Section Line
Lease Name: ROBINSON FARMS Well #: 30-1
County: SCOTT Total Vertical Depth: 5096 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4413		
CIBP		4880		
CIBP		4966		
SURF	8.625	414		WITH 280 SX CMT
DVT		2056		WITH 430 SX CMT
PROD	5.5	5096	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2011 12:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 272-1023

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS AT 4407'. IF CMT TO SURFACE IN 5 1/2" FILL 5 1/2" FROM 1380' TO SURFACE. CHACK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2011 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT WITH 100# HULLS & 15 FRAC BALL SEALERS AT 4395'. NO CIRCULATION. GOOD BLOW. PULL TBG TO 2149' & LOAD HOLE WITH 21 BBLS. PUMP 20 SX CMT AT 2149'. PULL TBG TO 1364' & CIRCULATE 5 1/2" CASING FULL OF CMT WITH 130 SX CMT. TOO H W/TBG. TOP OFF 5 1/2" CASING WITH 25 SX CMT. STAYED FULL. FILL 5 1/2" X 8 5/8" ANNULUS WITH 3 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4977	4983		
4904	4914		
4589	4596		
4407	4411		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG


District: 01

RECEIVED

JUL - 6 2011

KCC DODGE CITY

Signed



(TECHNICIAN)

RECEIVED
JUL 08 2011
KCC WICHITA

7/08