

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19238-00-00
Spot: W2NWSE Sec/Twnshp/Rge: 9-11S-15W
1980 feet from S Section Line, 2310 feet from E Section Line
Lease Name: LEBOW UNIT Well #: 8X
County: RUSSELL Total Vertical Depth: 3424 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225	0	150 SX
PROD	4.5	3419	0	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2011 11:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: BEREXCO, LLC Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 1550' - 950' - 450' - 175'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2011 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2790' - pumped 80 sxs cement with 300# hulls.
Pulled tubing to 1550' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 500' - pumped 30 sxs cement - cement circulated.
POOH. Hooked to casing and pumped 45 sxs cement.
Cement circulated out Braden head.

Perfs:

Top	Bot	Thru	Comments
3419	3424		OHIO
3414	3419		
3294	3296		
3268	3270		
3217	3219		
3166	3168		
3122	3124		
3106	3109		
3085	3087		
3048	3050		
3002	3006		
2962	2967		
2810	2816		

Remarks: ALLIED CEMENTING COMPANY-TICKET #039720.

Plugged through: CSG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

RECEIVED

JUN 17 2011

Form CP-2/3

7/08

KCC WICHITA

JUN 15 2011