

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-06142-00-01  
Spot: NESWNESW Sec/Twnshp/Rge: 16-11S-15W  
1707 feet from S Section Line, 1684 feet from W Section Line  
Lease Name: WHITSON Well #: 4  
County: RUSSELL Total Vertical Depth: 1055 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	186	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2011 7:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: DENNIS KRIMER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel.  
06/07/2011 - Rigged up and drilled on cement and rock into surface pipe (2 days).  
Drilled in the old hole with smaller bit - wall cake caved in hanging up tubing three or four times. Rigged up second mud pump and circulated wood chunks big and small.  
Started to run two shifts - made about 60' in 12 hrs. Both mud pumps had to be reworked. Bit trip and put on 7 1/4" bit - drilled down to 396'.  
06/13/2011 - got authorization from Wichita they could plug at 500'.  
The company wanted to drill thru the night.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/15/2011 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 1550' - pumped 35 sxs cement.  
Pulled tubing to 710' - pumped 80 sxs cement.  
Pulled tubing to 310' - pumped 85 sxs cement - cement circulated.  
06/14/2011 - 7:30a.m. - down to 496' - continued drilling down in to 1024'.  
06/15/2011 - 7:00am - started to loose circulation thru the night - had to get 80 bbls of mud from another location. (Had some easy drilling thru sand zone).  
Drilled down to 1055' - started to drill hard and losing return.  
At this point, decided to plug the well.  
Ordered cement truck and plugged as above.  
8 days and 2 nights drilling.  
TOP of anhydrite at 925' to 1006'.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #39631.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN)

CM

RECEIVED  
JUN 24 2011  
KCC WICHITA

JUN 17 2011

Form CP-2/3  
7/08