

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20031-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 27-1S-18W
4290 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BENNETT Well #: 1
County: PHILLIPS Total Vertical Depth: 3550 feet

Operator License No.: 30823

Op Name: CLARK, DARYL

Address: 240 W G ST
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218	0	160 SX
PROD	4.5	3548	0	125 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/08/2011 10:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: DARYL CLARK

Company: CLARK, DARYL

Phone: (785) 543-5727

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 6 sxs gel spacer.
10/18/1989 - Squeezed holes from 1190'-1219' w/65 sxs.
10/17/1989 - Squeezed holes from 942'-1219' w/100 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/08/2011 12:00 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2880' - pumped 6 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1800' - pumped 120 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 300# immediately.

Perfs:

Top	Bot	Thru	Comments
3385	3392		
3363	3367		

Remarks: ALLIED CEMENTING COMPANY-TICKET #39626.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

JUN 17 2011

Form CP-2/3

7/08

KCC WICHITA

JUN 14 2011