

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20396-00-00
Spot: SENWNW Sec/Twnshp/Rge: 29-1S-18W
1160 feet from N Section Line, 1245 feet from W Section Line
Lease Name: FISCHER B Well #: 1
County: PHILLIPS Total Vertical Depth: 1790 feet

Operator License No.: 30823
Op Name: CLARK, DARYL
Address: 240 W G ST
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	243	0	w/160 sxs cmt
PROD	4.5	1789	0	w/460 sxs cmt

Well Type: SWD UIC Docket No: D21707.0 Date/Time to Plug: 06/08/2011 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DARYL CLARK Company: CLARK, DARYL Phone: (785) 543-5727

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perfs at 1430' & 1490'.
Packer stuck in the hole at 1395'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2011 9:15 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing - pumped 150 sxs 60/40 pozmix - 4% gel with 500# hulls.
Max. P.S.I. 1500#. S.I.P. 1000#.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 50 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3408	3508		
1280	1820		

Remarks: ALLIED CEMENTING COMPANY-TICKET #39625.

Plugged through: CSG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

RECEIVED

JUN 17 2011

KCC WICHITA

JUN 14 2011

Form CP-2/3

7/08
cc to Bill
7/06