

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20066-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 23-1S-18W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: O'NEILL Well #: 3
County: PHILLIPS Total Vertical Depth: 3560 feet

Operator License No.: 30823

Op Name: CLARK, DARYL

Address: 240 W G ST
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	w/unknown sxs cmt
PROD	4.5	3558	0	150 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/08/2011 1:00 PM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: DARYL CLARK

Company: CLARK, DARYL

Phone: (785) 543-5727

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 6 sxs gel spacer.
Perforate at 1230' & 1730'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 06/08/2011 4:30 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3240' - pumped 6 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1875' - pumped 110 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus. Pressured up to 200#.

Perfs:

Top	Bot	Thru	Comments
3470	3474		
3392	3400		
3354	3361		

Remarks: ALLIED CEMENTING COMPANY-TICKET #39627.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

RECEIVED ✓
JUN 17 2011 7/08
Form CP-2/3

KCC WICHITA

JUN 14 2011