

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21705-00-00
Spot: SESWSENE Sec/Twnshp/Rge: 35-22S-23W
2650 feet from S Section Line, 960 feet from E Section Line
Lease Name: HODGEMAN-O'BRATE Well #: 2-35
County: HODGEMAN Total Vertical Depth: 3030 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/31/2011 1:30 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1410' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 80 SX CMT. 3RD PLUG AT 290' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 05/31/2011 3:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

****TRIED TO FISH COLLARS & GOT STUCK. WILL SHOOT OFF AT 2907' OR 2877'.****
1ST PLUG AT 1410' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 80 SX CMT. 3RD PLUG AT 290' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED

JUN 15 2011

KCC WICHITA

District: 01

RECEIVED
JUN - 9 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-28