

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01334-00-00
Spot: NWSESW Sec/Twnshp/Rge: 6-24S-5E
977 feet from S Section Line, 3492 feet from E Section Line
Lease Name: CLAUSSEN Well #: 7
County: BUTLER Total Vertical Depth: 2466 feet

Operator License No.: 7228
Op Name: BRICKLEY, DONALD DBA D & J INVES
Address: 128 N ALLEGHANY PO BOX 107
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	190		75 sxs cement
PROD	5.5	2464	792	75 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2011 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: JOHN BRICKLEY Company: _____ Phone: (316) 371-1896

Proposed Plugging Method: 6 sx cement w/ dump bailer on bottom, pull top 300' pipe, run 2" tubing to rock bridge @ 250', pump to top (surface).

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 05/18/2011 1:00 PM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

OPERATOR SPOTTED 25 SX @ 2325' AND TAGGED CEMENT NEXT DAY AT 2250' AND TUBING PULLED. CASING WAS SHOT 5 TIMES AND 792' OF CASING WAS RECOVERED. 2" TUBING WAS RAN BACK INTO HOLE, CEMENT WAS CIRCULATED FROM 290' TO SURFACE, AND 5 SX USED TO TOP OF WELL.

Perfs:

Remarks:
Plugged through: CSG

RECEIVED
JUN 10 2011
KCC WICHITA

District: 02 Signed [Signature] (TECHNICIAN)

JK