

15-051-00019-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
500 Bittling Building
Wichita, Kansas

Ellis County, Sec. 17 Twp. 14 Rge. 16 NE 1 (W)
Location as "NE/CNWxSWx" or footage from lines SW SE NE
Lease Owner Musgrove Petroleum Corporation
Lease Name ROHLEDER Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed June 20, 19 52
Application for plugging filed May 14, 19 54
Application for plugging approved May 17, 19 54
Plugging commenced May 26, 19 54
Plugging completed May 26, 19 54
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production May 8, 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224'	
				5-1/2"	3443 1/2'	2553'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled well with sand from 3265' to 3200'.
Dumped 4 ex cement. Filled to 3175'. Pumped
35 ex mud, released plug, then pumped 70 ex
cement into surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Casing Pulling Company,
Address Russell, Kansas.

STATE OF Kansas COUNTY OF Sedgwick ss.
I, Gordon L. Koelling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 54

My commission expires July 16, 1955.

Alvin E. Rouse
Notary Public.

PLUGGING
FILE SEC 17-14-R-16W
BOOK PAGE 34 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1954
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Bohleder #1
 LOCATION: SW SE NE Section 17-14S-16W
 Ellis County, Kansas
 COMMENCED: June 7, 1952
 COMPLETED: June 20, 1952

0	105	Sand, sandy shale collar & pyrite
105	210	Sand & clay
210	235	Shale
235	250	Sand
250	615	Shale
615	640	Sand
640	1035	Shale & redbed
1035	1065	Iron & Anhydrite
1065	1195	Shale & redbed
1195	1630	Shale
1630	1810	Shale & shells
1810	1935	Shale
1935	2030	Shale & lime streaks
2030	2090	Lime w/shale streaks
2090	2500	Lime & shale
2500	2620	Shale
2620	2770	Lime streaks & shale
2770	3022	Shale & lime
3022	3137	Lime
3137	3407	Lime & shale
3407	3431 1/2	Lime & shale---irregular
	3431 1/2	Rotary Total Depth

Set 224' of 8-5/8" surface casing, cemented with 115 sacks.
 Set 3443.54' of 5-1/2", cemented with 130 sacks.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Bohleder #1, Section 17-14S-16W, Ellis County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By: Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 30th day of June, 1952.

Thayer Lee Rayer
 Notary Public

My commission expires: July 9, 1952.

PLUGGING
 FILE SEC 17 T 14 N 16W
 BOOK PAGE 34 LINE 30

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 15 1954
 CONSERVATION DIVISION
 Wichita, Kansas