

15-051-30026-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 15 Twp. 14 Rge. 16 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SE SW SW
Lease Owner Specter Pine & Supply, Inc.
Lease Name Witt Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed March 4, 1965 19____
Application for plugging filed 1-14-66 19____
Application for plugging approved 1-17-66 19____
Plugging commenced 1-24-66 19____
Plugging completed 1-26-66 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation arbuckle Depth to top 3399' Bottom 3479' Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	201'	None
				5-1/2"	3479'	2730'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3480', sanded to 3465' and dumped 3 sacks of cement @ 3465' with dump bailer. Pulled 5 1/2" casing, set plug @ 480', set rock bridge to 470' and dumped 25 sacks of cement @ 470'. Bailed fluid to 200', set rock bridge to 190' and dumped 25 sacks of cement @ 190'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1966
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1966

My commission expires May 20, 1968
Milton J. Tolson Notary Public.

15-051-30026-00-00
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


COPY

Company **C.L. MILES & WITT FARM CO.**
 Farm **Witt** No. **1**

SEC. **15** T. **14** R. **16W**
 SE SW SW

Total Depth. **3480'**
 Comm. **12-14-64** Comp. **3-4-65**
 Shot or Treated.
 Contractor. **A.L. JACKSON DRLG. CO.**
 Issued. **4-24-65**

County **Ellis**
KANSAS



CASINO:

8 5/8" 201'
5 1/2" 3479' w/125 sx cam.

Elevation. **1904' K.R.**

Production. **Pmp. 12 BO & 30 BWPD**

Figures Indicate Bottom of Formations.

Post rock shale, shells	267
shale, shells, red bed,	
strks of sand	1000
Anhydrite	1039
shale	1450
shale, shells	1680
lim. shale	1890
limestone, shale	2025
lime, shale	2045
hard, sharp lime, shale	
	2080
shale, lime	2539
shale, shells	2685
shale, lime	2822
lime; Topoka, shale	2910
lime, shale	2973
lime	3105
lime, shale	3155
lime	3160
lime, shale	3295
lime	3318
lime, Arbuckle 3398	3400
lime, cherty conglomerate	
	3415
lime	3430
lime, chert	3440
Arbuckle	3445
lime	3480
Total Depth	

TOPS: SCOUT	SAMPLE
Haebnar	3089
Toronto	3118
Lansing	3142
Conglom erate	3390
Arbuckle	3399

RECEIVED
 STATE GEOLOGICAL SURVEY
 JAN 17 1966
 CONSERVATION DIVISION
 Wichita, Kansas