

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
213 No. Market  
Wichita, Kansas

15-051-01516-00-00  
WELL PLUGGING RECORD

Form CP-40P

Ellis County, Sec. 15 Twp. 14 Rge. 16 (E) W (W)  
NE SW NW

Location as "NE/CNWxSWx" or footage from lines \_\_\_\_\_  
Lease Owner Clinton Oil Company  
Lease Name Robben Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 19 19 64  
Application for plugging filed November 18 19 66  
Application for plugging approved November 22 19 66  
Plugging commenced 12/19/66 19 \_\_\_\_\_  
Plugging completed 12/21/66 19 \_\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production November 1 19 66  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well L. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3485 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	none
				4 1/2	3484	2649.39'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

XXXX Raised mast, checked hole to 3179', ran sand to 3125. Mixed and dumped 4 sacks of cement. Dug cellar and rigged up over 4 1/2". Worked tension to 15", had hole loaded. Shot pipe at 2644, worked pipe loose, pulled 34 joints of plastic pipe, 6 joints of plain. Pulled 42 joints of 4 1/2" casing, loaded junk, lowered mast and racked unit. Pumped in 25 sacks of mud and 85 sacks of cement.


DEC 20 1966  
12-29-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 24 day of Dec, 1966  
Julius M. ...  
Notary Public.



Company: Clinton Oil & Jones-Gebert Oil, Inc.  
 Contractor: Jones-Gebert Oil, Inc.  
 Farm: #1 Robben, NE SW NW  
 Section 15-148-16W  
 Ellis County, Kansas

Commenced: 3/7/64  
 Completed: 3/19/64  
 Casing: 8-5/8" at 200' with 160 sx.  
 4-1/2" at 3484' with 160 sx.

0	=	100	Sand, Shale & Clay
100	-	150	Shale & Sand
150	-	200	Shale
200	-	465	Shale & Shells
465	-	1470	Shale
1470	-	1707	Shale & Shells
1707	-	2035	Shale
2035	-	2090	Lime
2090	-	2568	Lime & Shale
2568	-	2760	Shale
2760	-	3166	Lime & Shale
3166	-	3220	Lime
3220	-	3235	Kansas City
3235	-	3442	Lime
3442	-	3485	Arbuckle
		3485	Rotary Total Depth

**RECEIVED**  
 STATE GEOLOGICAL COMMISSION  
 NOV 28 1966  
 CONSERVATION DIVISION  
 Topeka, Kansas

I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Robben, NE SW NW, Section 15-148-16W, Ellis County, Kansas, as reflected by the files of Jones-Gebert Oil, Inc.

  
 \_\_\_\_\_  
 George R. Jones

State of Kansas )  
 ) ss:  
 County of Sedgwick)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this twenty-fourth day of March, 1964.

My Commission Expires:  
 January 8, 1968

  
 \_\_\_\_\_  
 Lois J. McCoy, Notary Public