

15-051-60006-00-00


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 15 Twp. 14 Rge. 16 (E) (W)

Location as "NE/CNWxSWx" or footage from lines NW SE NW
Lease Owner Red Barron Production Company
Lease Name Robben Well No. #1
Office Address P. O. Box 55, Phillipsburg, Kansas 67667
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-10 19 69
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "
Reason for abandonment of well or producing formation Dry Hole " " "

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1970
CONSERVATION DIVISION
Wichita, Kansas


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

347 1/2	-	550	-	Heavy Rotary Mud
		550	-	Plug, 25 sacks cement
550	-	280	-	Heavy rotary mud
		280	-	Plug, 25 sacks
280	-	40	-	Heavy rotary mud
40	-	GL	-	Plug, 1 sack hulls, 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address Box 359, Hoisington, Kansas 67544

STATE OF KANSAS COUNTY OF Barton, ss.
Peel Brothers, Inc. (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Wendell C. Peel
Wendell C. Peel, President
(Address)



SUBSCRIBED AND SWORN TO before me this 2 3rd day of October, 19 69

My commission expires

6-21-70

Ethel S. Williamson
Ethel S. Williamson
Notary Public.

15-051-60006-0000

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1970
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Well Owner: Red Barron Producers
Farm Name: Robben #1
Date Started: 9-30-69
Date Completed: 10-10-69
Total Depth: 3474'

Casing: 8-5/8" set at 283' cemented

Contractor: Peel Brothers, Inc.

Section 15-14S-16W
Ellis County, Kansas

Bottoms of formations are as follows -

Surface Shale and Sand	0 - 45
Post Rock	- 95
Sand	650
Red Bed and Shale	785
Shale	1016
Anhydrite	1057
Shale and Shells	1290
Lime and Shale	3020
Lime	3474
Total Depth	3474

This is to certify that the above information is true and correct to the best of our knowledge.

PEEL BROTHERS, INC.

Wendell C. Peel
Wendell C. Peel
President



SUBSCRIBED AND SWORN to before me this 23rd day of October, 1969.

Ethel S. Williamson
Ethel S. Williamson
Notary Public

My Commission expires 6-21-70