


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Ellis County. Sec. 14 Twp. 14S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Chief Drilling Co., Inc.
Lease Name ROBBEN Well No. 1
Office Address Box 797 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/1/1965
Application for plugging filed 3/1/1965
Application for plugging approved 3/1/1965
Plugging commenced 3/1/1965
Plugging completed 3/1/1965
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	199	8-5/8	199	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 540'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 180'
Mixed 20 sacks cement through drill pipe
Hulls & wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1965

03-04-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 797 - Great Bend, Kansas

(Address)

Subscribed and Sworn to before me this 2nd day of March, 1965

My commission expires Jan. 26, 1967

Carmen R. Cook
Carmen R. Cook, Notary Public.

13-051-30025-00-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

ROBBEN #1
NE NE NW Sec. 14-14S-16W
Ellis County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 2/22/65
Completed: 3/1/65

Casing Record: 8-5/8" @ 199' w/150 sacks Sunset & 3 sacks Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
			1905 Gr.
			1908 D.F.
			1910 K.B.
			<u>FORMATION TOPS</u>
Surface Sand & Gravel	0	199	Anhydrite 1002 + 908
Shale & Sand	199	895	Howard 2822 - 912
Red Bed	895	1002	Severy Shale 2872 - 962
Anhydrite	1002	1038	Topeka 2888 - 978
Shale & Shells	1038	1295	Heebner 3111 - 1201
Shale	1295	1673	Toronto 3132 - 1222
Shale & Lime	1673	1910	Lansing 3162 - 1252
Lime	1910	2340	Base Kansas City 3390 - 1480
Lime & Shale	2340	2888	Conglomerate 3400 - 1490
Lime	2888	3390	Total Depth 3460 - 1550
Shale	3390	3400	
Conglomerate	3400	3460	
Total Depth	3460		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NE NW Section 14-14S-16W, Ellis County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 2nd day of March, 1965.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.

FILED
STATE OF KANSAS, COUNTY OF BARTON

MAR 4 1965

CONSERVATION DIVISION
Wichita, Kansas