


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-01267-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 10 Twp. 14 Rge. 16 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines NE, NE SW  
Lease Owner Shields Oil Producers  
Lease Name Kuhn Well No. 1  
Office Address Shields Bldg., Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 27 1957  
Application for plugging filed March 27 1957  
Application for plugging approved March 27 1957  
Plugging commenced March 27 1957  
Plugging completed March 27 1957  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3488 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	270	Cmtd. w/125 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud to 265'  
Set bridging plug @ 265' w/ 1/2 sax hulls on plug  
Dump 20 sax cement thru 4 1/2" drill pipe  
Heavy mud to 40'  
Set bridging plug @ 40' w/ 1/2 sax hulls on plug  
Dump 10 sax cement to cellar

RECEIVED

04-02-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.  
Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
R. J. Shields (Employee of ~~owner~~) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Shields

Shields Bldg., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of March, 1957.

Jack P. Beaman  
Notary Public.

My commission expires 12-18-1957

24-7866-B 3-53-20M

PLUGGING  
FILE SEC 10 T 14 R 16 W  
BOOK PAGE 3 L.I.E. 2



Shields

15-051-01267-00-00

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers  
 Well: Kuhn #1  
 Commenced: March 13, 1957  
 Completed: March 27, 1957  
 Contractor: Shields Drlg. Co., Inc.

Well Description: NE NE SW  
 Sec. 10-14S-16W  
 Ellis County, Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	270'	Cmtd. w/125 sax

Elevation: 1927' RB

Treatment:

Production: D & A

Taps:	Heebner	3130'
	Toronto	3143'
	Lansing-KC	3175'
	Ch. Conglomerate	3425'
	Arbuckle	3436'

..... Figures Indicate Bottom of Formations .....

Surface Clay	15
Post Rock	20
Shale	40
Clay & Shale	270
Shale & Shells	565
Sand	650
Red Bed	945
Shale	1018
Anhydrite	1060
Shale	1232
Shale & Shells	1695
Lime & Shale Streaks	1830
Shale & Lime	1925
Lime & Shale	2065
Lime	2120
Lime & Shale	2220
Lime & Shale Streaks	2355
Shale & Lime	2585
Shale	2730
Shale & Lime	2930
Lime	3448 RTD

RECEIVED  
STATE CORPORATION COMMISSION

APR 2 - 1957

CONSERVATION DIVISION  
Wichita, Kansas

Notes

DST #1 3437 - 3448 Tool open 1 hr. w/weak intermittent blow thruout.  
Rec. 120' mud. BHP - 918#/20 min.

PLUGGING			
FILE	SEC 10	T 14	R 16W
BOOK	PAGE 3	LI 2	2