


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-051-20464-00-06
Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 6 Twp. 14S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines NE SE NE
Lease Owner Range Oil Company, Inc.
Lease Name John Kippes Well No. 1
Office Address 402 Insurance Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 19, 19 69
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced July 19, 19 69
Plugging completed July 19, 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey of Hays
Producing formation Depth to top Bottom Total Depth of Well 3505 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	220'	8-5/8"	220'	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from Total Depth to 500 Feet,
Plug and 50 sax Cement; Mud to
210 Feet, Plug and 25 sax Cement;
Mud to 40 Feet, Plug bridged with
Kelly and 10 sax Cement to Base
of Cellar. Job completed at
6:30 P.M. 7/19/69.

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Globe Oilwell Cementing Co.
Address Box 628, Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of July, 19 69

My commission expires November 26, 1970.

Louise K. Whitted - Notary Public.

DRILLERS LOGJOHN KIPPES NO. 1


CASING RECORD:	OPERATOR: Range Oil Company	DESCRIPTION:
8-5/8" @ 220'	CONTRACTOR: Sage Drilling Co.	NE SE NE
w/100 sax cement	COMMENCED: July 11, 1969	Sec. 6-14S-16W
TOTAL DEPTH:	COMPLETED: July 19, 1969	Ellis County,
3505'		Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	214	
Shale & Shells	214	400	
Sand	400	532	
Hard Sand	532	540	
Dark Sand	540	695	
Shale, Shells & Redbed	695	1085	
Anhydrite	1085	1125	
Shale & Shells	1125	1810	
Shale & Lime	1810	2145	
Lime & Shale	2145	3155	
Lime	3155	3505	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 22nd day of July, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1969
CONSERVATION DIVISION
Wichita, Kansas