

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-015-01179-00-00  
051

WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 14 Rge. 16 (D) (W)

Location as "NE/CNW/4SW/4" or footage from lines NW NW SE  
Lease Owner **Buick Drilling Inc., et al**  
Lease Name **Dreiling** Well No. **1**  
Office Address **409 Wolcott Bldg., Hutchinson, Kansas**  
Character of Well (completed as Oil, Gas or Dry Hole) **dry hole**  
Date well completed **May 17, 19 58**  
Application for plugging filed **May 17, 19 58**  
Application for plugging approved **May 17, 19 58**  
Plugging commenced **May 17, 19 58**  
Plugging completed **May 17, 19 58**  
Reason for abandonment of well or producing formation **dry hole**  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **yes**



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well **Eldon Petty**  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well **3502** Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

**Back to 500 heavy rotary mud 1 Howco plug 1/3 sack hulls with 20 sacks cement placed through drill pipe. Bottom plug back to 210' 1 Howco plug 1/3 sack hulls with 20 sacks cement placed through drill pipe. From plug #2 back to 40' heavy rotary mud 1 Howco plug 1/3 sack hulls with 10 sacks cement.**

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor **Buick Drilling Inc.**  
Address **409 Wolcott Bldg., Hutchinson, Kansas**

STATE OF **Kansas**, COUNTY OF **Reno**, ss.  
**H. R. Buick** (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Buick*  
**409 Wolcott Bldg., Hutchinson, Kansas**  
(Address)

SUBSCRIBED AND SWORN to before me this **20th** day of **May**, 19 **58**.

*Wilma A. Clark*  
**Wilma A. Clark** Notary Public.

My commission expires **November 16, 1961**

23-8390-s 6-51-20M

MAY 23 1958  
05-23-58  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 6 T. 14 R. 16W  
BOOK PAGE 102 LINE 34

W E L L L O G

Drilling #1 NW NW SE 6-11-16  
Ellis County, Kansas

COMPANY: Buick Drilling Inc., et al

CONTRACTOR: Buick Drilling Inc.

COMMENCED: May 7, 1958

COMPLETED: May 17, 1958

CASING: 225' of 8 5/8"

ELEVATION: 1959 K.B.

<u>DEPTH</u>	<u>FORMATION</u>
0- 225	Surface
225- 310	Clay and shale
310- 760	Red bed and sand
760- 885	Shale and shells
885-1060	Red bed and sand
1060-1090	Shale and sand
1090-1110	Shale
1110-1165	Anhydrite
1165-1745	Shale and shells
1745-1765	Lime
1765-2215	Lime and shale
2215-2350	Shale
2350-2750	Lime and shale
2750-2845	Shale
2845-3220	Shale and lime
3220-3462	Lime
3462-3502	Lime and shale
3502	Total depth

## DRY AND ABANDONED

TOPS

Heebner shale	3175
Lansing	3220
Conglomerate (cherty)	3466
Weathered Arbuckle	3479
Arbuckle (solid) ?	3494

I, H. R. Buick, certify the above to be a true and correct copy of the Driller's Log of the said well, according to the records of this office.

*H. R. Buick*  
H. R. Buick -- President  
BUICK DRILLING INC.

RECEIVED  
STATE GEOLOGICAL COMMISSION

MAY 23 1958

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 6 T. 14 R. 16W  
BOOK PAGE 102 LINE 34