

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 6 Twp. 14S Rge. 16W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE SE SE

Lease Owner Victor Drilling, Inc.

Lease Name A. J. Dreiling Well No. 1

Office Address 301 Koch Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed May 7 19 54

Application for plugging approved 19


Plugging commenced May 11 19 54

Plugging completed May 14 19 54

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	158'	None
				5-1/2"	3468'	2687'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3480' to 3460' and ran 4 sacks of cement. Halliburton Cementing Company pumped in 35 sacks of mud and 65 sacks of cement to fill to top. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1954 06-23-54
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Kansas COUNTY OF Sedgewick ss.

I, P. J. Gallagher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. J. Gallagher

301 Koch Bldg. Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 54

My commission expires August 18 - 19 54 Sylvia Rhinehart Notary Public.

PLUGGING
FILE SEC 6 T 14 R 16W
BOOK PAGE 33 LINE 2

VICTOR DRILLING, INC.

No. 1 A. P. Drilling

SE SE SE Sec. 6-14-16
Ellis County, Kansas

Spud. 11-30-52

Comp. 12-12-52

8 5/8" 158' 80 sax cement
5 1/2" 3468' 150 sax cement

Elev. 1956 K.B.

surface shale, shells, gravel	0-340
red bed	350
sandy red bed	500
sand	675
red bed	1070
sand & lime	1125
shale & gip	1155
shale & shells	1785
broken lime & shale	1870
lime	2270
shale & lime	2640
shale	2765
lime & shale	3072
lime	3352
dense lime	3389
lime	3462
conglomerate	3470
Arbuckle	3480
Total Depth	3480

STATE OF KANSAS))
) SS:
COUNTY OF SEDGWICK)

I, Patrick F. Gallagher, swear that to the best of my knowledge the foregoing information is correct.

Patrick F. Gallagher
Patrick F. Gallagher

Subscribed and sworn to before me, a notary public, this ²³ day of June
~~May~~, 1954.

Sylvia Rhinehart
Notary Public

My commission expires
Aug. 18-1954.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1954
CONSERVATION DIVISION
Wichita, Kansas

