



15-167-20920-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company has this date requested permission to plug the following described well:

Mr. F. W. Vishnefske guarantees payment of the plugging fee.

Operator's full Name: Saline Basin Petroleum Co.

Complete Address: 119 S. Santa Fe, Salina, Kansas

Lease Name: Steinle "B" Well No. # 1

Location: NW NE NE Sec. 22 Twp. 14 Rge. 11 (E)(W) W

County: Russell Total Depth 2925 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" csg. 282' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 260' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & 10 sax cement with

Allied Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

David L. Luman
Conservation Division Agent