



15-167-20601-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 4 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company has this
date requested permission to plug the following described well:

Mr. F. W. Vishneske guarantees payment of the plugging fee.

Operator's full Name: F. W. Vishneske or Saline Basing Pet. Co.

Complete Address: 119 S. Santa Fe, Salina, Kansas

Lease Name: Bunker Well No. # 1

Location: SW NE SW Sec. 21 Twp. 14 Rge. 11 (E)(W) W

County: Russell Total Depth 3175 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" csg. 283' Ccu.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 280' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & 10 sax cement with

Allied Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Luman
Conservation Division Agent