



15-1169-20120-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

February 10, 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Melville Farmer of Big Springs Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: F & M Oil Company, Inc.

Complete Address: 422 Union Center, Wichita, Kansas 67202

Lease Name: Thelander Well No. 1

Location: SE SE NW Sec. 22 Twp. 14 Rge. 2 (~~E~~) (W)

County: Saline Total Depth: 3410'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Farmer was instructed to plug the well as follows:

8 3/8" - 249' - 175 sacks Common 32-29. Fill hole with mud.  
Pump 50 sacks 50-50 Perm. w/4% gel + 3% cal. chloride through  
drill pipe at 300'. Fill hole with mud to 40'. Push plug  
and 1/2 sack hulls to 40' and cap hole with 10 sacks  
Cement. Cement rat hole with 5 sacks.

Very truly yours,

[Signature]  
Conservation Division Agent

RECEIVED  
FEB 17 1981  
02-17-1981  
CONSERVATION DIVISION  
Wichita, Kansas