



15-1109-20119-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water

WICHITA, KANSAS 67202

February 19, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Melville Farmer of Big Springs Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Patton Oil Company

Complete Address: 5660 Syracuse Circle, Suite 200, Englewood, Colorado 80110

Lease Name: Thelander Well No. 1

Location: C NE SW Sec. 22 Twp. 14 Rge. 2 (E) (W)

County: Saline Total Depth: 3402'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Farmer was instructed to plug the well as follows:

8 5/8" - 223-175 sacks comman-32% gel-2% cal chlor. Fill hole with mud. Pump 50 sacks 50-50 Poz mix w/4% gel +32% cal chloride through drill pipe at 300'. Fill hole with mud to 40'. Push plug and 1/2 sack balls pushed to 40' and hole cemented to base of cellar with 10-sack. Rathole cemented with 5 sacks

Very truly yours,

FEB 24 1981
02-23-1981
CO. REGISTRATION DIVISION
WICHITA, KANSAS

William J. Roman
Conservation Division Agent