

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # 15-109-20,554 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Overland Exploration Company KCC LICENSE # 30798

ADDRESS 200 E. First, Ste 505 CITY Wichita  
(owner/company name) (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-6391

LEASE Peters WELL# 2 SEC. 36 T. 14S R. 33 (East/West)

20' E of - SW -NE NW SPOT LOCATION/QQQQ COUNTY Logan

4290' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

3610' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  DGA  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 244.58' CEMENTED WITH 60-40pos. - 175 sx SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUGS \_\_\_\_\_

ELEVATION 2835'-2840' T.D. 4520' ANHYDRITE DEPTH 2260'-2281'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2260' w/25 sx; 2nd plug @ 1135' w/100 sx; 3rd plug @ 290' w/40 sx; 4th plug @ 40' w/10 sx; rathole 15 sx; Ttl 190 sx 60-40 posmix 6% gel 2 sx Floseal.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED?

If not explain why? Sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# (913) 743-5654

ADDRESS P.O. Box 103 City/State Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

(company name) (contractor's)  
ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 8:00 a.m. 9-12-93

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: \_\_\_\_\_ AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)