

15-051-00418-00-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 39-8  
LOCATION NW SE SE  
SEC. 9 TWP. 14 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Goetz

Operator Birmingham-Bartlett Address 300 Kaufman Bldg Wichita,

Field \_\_\_\_\_ County Ellis

Total Depth 3551 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 181' circulated with cement - 5 1/2" 3530' with 125 sax

cement behind - P.B. 3533', perforated 3528',

Filled with sand to 3515', set 4 sax cement with dump bailer,

pulled 3000' 5 1/2" - circulated hole with heavy mud through 5 1/2" -

(35 sax Gel), set cementing plug at 550', displaced 20 sax cement through

5 1/2" - heavy mud to 220', set cementing plug and displaced 15 sax cement

through 5 1/2" - heavy mud to 55', set rock and 10 sax cement to bottom

cellar. Mudding and Cementing by Sun Cementing Co.

District Conservation Agent

Date 8-27-57 *Eldon Kelley*

PLUGGING  
FILE SEC 9 T. 14 R. 17W  
BOOK PAGE 24 LINE 8

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1957  
08-29-1957  
CONSERVATION DIVISION  
Wichita, Kansas