

15-063-20021-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,
 Complete Address 905 Century Plaza, Wichita, Kansas.
 Lease Name E. Long Well No. 1
 Location CNE-NW Sec. 15 Twp. 14 Rge. (E) (W) 27
 County Gove Total Depth 4405'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Rockhold Engineering, Incorporated,
 Address Box #698, Great Bend, Kansas. License No. 670
 Operation Completed: Hour 1:00 PM Day 3 Month 11 Year 1971

The above well was plugged as follows:

272'--8 5/8" Surface cement circulated.
4405'--5 1/2" Production casing cemented on bottom with 135 Sx. No plug back indicated.
Top perforations @ 4300'.

Sanded well back to 4250' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(600') and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed
with 100 Sx. cement from 1000' to 675' then 9 sacks gel from 675' to 300' and followed
with 25 Sx. cement from 300' to 225' then 5 sacks gel from 225' to 25' and finally 10
Sx. cement from 25' to bottom of cellar. Maximum pump-in pressure-250#. Final shut-in
pressure-75#. (Mudding and cementing operations by Allied Cementing, Inc.,).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 11-11-71

WELL NO. 4613-W