

15-063-20166-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1973
04-05-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Tomlinson Oil Company, Incorporated,
Complete Address Suite 1030, 200 West Douglas, Wichita, Kansas.
Lease Name Rhoades Well No. 1
Location SE-NW-NE Sec. 11 Twp. 11 Rge. (E) (W)27
County Gove Total Depth 4390'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor John O. Farmer, Incorporated,
Address 370 W. Wichita, Russell, Kansas. License No. _____

Operation Completed: Hour 11:30 AM Day 4 Month 4 Year 1973

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. D. Nichols
Well Plugging Supervisor

INVOICED
DATE 4/5/73
INV. NO. 7218-W