

15-063-20068-00-00

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company,
Complete Address 705 Fourth National Bank Building, Wichita, Kansas.
Lease Name Balzerick Well No. B-1
Location CNE-SW Sec. 13 Twp. 14 Rge. (E) (W) 27
County Gove Total Depth 4375'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 2:20 AM Day 26 Month 5 Year 1971

The above well was plugged as follows:

272'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru
DP from 1000' to 675'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-28-71
INV. NO. 3761-W

Signed: W. L. Nichel
Well Plugging Supervisor