

15-063-20080-00-00

Form CP-3
Rev. 6-4-68

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name R. Jones Well No. 1

Location SE-NE Sec. 11 Twp. 11 Rge. (E) (W) 27

County Gove Total Depth 3725'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:00 AM Day 17 Month 8 Year 1971

The above well was plugged as follows:

265'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 960' and displaced 100 Sx. cement thru
DP from 960' to 635'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from 275'
to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Dinkel*
Well Plugging Supervisor

8-20-71
4188-W